#### City of Calistoga 1 Staff Report 2 3 4 TO: Honorable Mayor and City Council FROM: 5 Derek Rayner, Senior Civil Engineer VIA: Michael Kirn, Public Works Director/City Engineer 6 7 DATE: September 15, 2015 8 Consideration of a Resolution Awarding a Construction Contract to SUBJECT: 9 Maggiora & Ghilotti, Inc. for the Emergency River Bank Repair for the Feige 10 Tank Water Main and Authorizing the City Manager to Execute the Contract APPROVAL FOR FORWARDING: 11 Brod-Br 12 13 RICHARD D. SPITLER, CITY MANAGER 14 15 **ISSUE:** Consideration of a Resolution that: 16 1. Conditionally awards the construction contract to Maggiora & Ghilotti, Inc. for the 17 18 Emergency River Bank Repair for the Feige Tank Water Main Project in the 19 amount of \$79,440, subject to Maggiora & Ghilotti, Inc. providing all documents in satisfaction of the bid award requirements. 20 21 22 2. Approves the total project construction budget in the amount of \$93,390, which includes a contingency of 10% of the bid amount, permit administration, and 23 24 construction staking costs and authorizes the Public Works Director to negotiate and approve contract change orders up to the approved construction budget 25 26 amount. 27 28 3. Authorizes the City Manager to execute the Project contract on behalf of the City 29 of Calistoga. 30 31 4. Directs staff to issue a notice of award to Maggiora & Ghilotti, Inc. and otherwise administer the Project. 32 33 34 **RECOMMENDATION**: Adopt the Resolution.

35

 **BACKGROUND / DISCUSSION:** City staff discovered the bank along Cyrus Creek is severely eroding and has exposed support caissons that hold up the 14-inch domestic water line that serves as Feige tanks only inlet/outlet. The tank's water main is located on a narrow private road (City has easement for waterline). This road is the City's only way to access Feige Reservoir. If the piles become any more exposed the water main will collapse, and result in catastrophic failure; access to Feige Tank may also be impossible (see photo below):



If the water main fails it could potentially drain all of the City's stored domestic drinking water (from both Mt Washington Tank and Feige Tank), depending on how quickly staff is able to isolate and close off valves.

Staff hired Prunuske Chatham, Inc. to design a bank repair to fix this eroded section and protect the water main from failure. In order to protect this main the river bank repair needs to be completed prior to this winter season.

We recommend construction begin this September so that it can be completed by mid-October. The design has been completed and staff has requested bids from six contractors: Argonaut Constructors, Granite Construction, Maggiora & Ghilotti, Inc, Harold Smith, Wilson Construction, Blakely Construction and Dennis Watson Construction. Since this is such a tight schedule, we only received one bid from M&G for \$79,440.

Staff is trying to be proactive to alleviate a potentially catastrophic event to the City's critical water infrastructure and highly recommends that Council adopt this resolution.

#### **CONSISTENCY WITH CITY COUNCIL GOALS AND OBJECTIVES AND CEQA:**

The recommended action supports the FY 2015/16 City Council Goal No. 3, Objective 1 and 2:

 Maintain the high level of service and reliability of the City's infrastructure systems and facilities

Upgrade and maintain the long-term reliability of the City's water system

This repair is considered a "statutory exemption" from CEQA per Guidelines Section 15269.

The project is also permitted under an emergency Army Corp permit (Regional General Permit 5) that also covers Fish and Wildlife and State Regional Board permits.

#### **FISCAL IMPACT:**

The total construction cost is estimated at \$93,390 broken down as follows:

| Construction Contract: | \$79,440 |
|------------------------|----------|
| Contingency at 10%:    | \$ 7,950 |
| Permit Administration: | \$3,500  |
| Construction Staking   | \$2,500  |

This project was approved in the FY15/16 budget as a Major Capital Improvement Project in the amount of \$130,000, funded through Measure A. The City will also apply for Cost Share program through County Flood Control District and hopes to receive up to \$30,000 for the repair. If successful Measure A monies expenditures would amount to \$63,390.

#### ATTACHMENTS:

- 1. Resolution
- 2. Plan Sheet for Repair

WHEREAS, the project will use Measure A funds and Staff will also apply for the

Cost Share Program through the Napa County Flood Control District for \$30,000; and

44

45

46


KATHY FLAMSON, City Clerk


92

WHEREAS, funds for the Emergency Feige River Bank Repair Project are budgeted in FY 2015/16 Streets Capital Improvements (01-5523). Total construction costs are expected to be \$93,390, which includes construction, construction contingency, permit administration and construction staking; and WHEREAS, Staff recommends that the bid be awarded to Maggiora & Ghilotti, NOW, THEREFORE BE IT RESOLVED by the City Council of the City of 1. Finds that the bid from Maggiora & Ghilotti, Inc. is the lowest responsive bid and is a responsible bidder and waives any and all minor bid irregularities. 2. Approves the Project construction budget in the amount of \$93,390, which includes a contingency of 10% of the bid amount and authorizes the Public Works Director/City Engineer to negotiate and approve contract change orders 3. Awards the construction contract to Maggiora & Ghilotti, Inc. in the amount of \$79,440 for construction of the Emergency River Bank Repair for the Feige Tank Water Main Project conditioned upon Maggiora & Ghilotti, Inc. providing all documents in satisfaction of the bid award requirements. 4. The City Manager is hereby authorized to execute the Contract on behalf of the City of Calistoga, subject to approval as to form by the City Attorney. 5. Directs staff to issue a notice of award to Maggiora & Ghilotti, Inc. and PASSED, APPROVED, AND ADOPTED by the City Council of the City of Calistoga at a regular meeting held this 15<sup>th</sup> day of September 2015, by the following **CHRIS CANNING, Mayor** 

**ROCK SLOPE PROTECTION** 

# **ATTACHMENT 2**





2+30.00

APPROXIMATE LOCATION OF (E) BANK SUPPORT STRUCTURE

FR 1.5: FABRIC REINFORCED


-TRANSITION FROM RSP

(RS) I: ROCK SLOPE

PROTECTION

TO FREF AT EL. 93'

DESIGN CONDITION



## LIVE CUTTING NOTES FOR WILLOW

- APPR*O*XIMATE

LOCATION OF 14" (E) WATER LINE

## 1.0 Cutting and Collecting

- 1.1 The contractor shall supply local willow from live native stands of salix. Material shall be collected as close to the site as possible. Strip all leaves immediately after cutting.
- 1.2 All cuts shall be clean cuts with no bark peeling and no material splitting. Cut the bottom of material at an approximate 45° angle to ensure cuttings are not placed upside down and for easier installation.
- 1.3 Place cut material in bundles of 25 or 50 with buds facing up and angled cut bottoms down at the collection site for inventory, easy handling and protection during transport. 1.4 If material is collected onsite, 66% of the parent material must remain intact with clean flush cuts to main body of tree, allowing for regeneration.
- 1.5 Cuttings shall remain moist and in shade at all times. 1.6 Rooted willow poles and stakes may be substituted for live poles and stakes.

# 2.0 Transportation

- 2.1 Live cutting bundles shall be placed in an organized fashion to prevent damage during loading and unloading of vehicles or trailers.
- 2.2 Cuttings must be covered and protected from wind and sun during transportation. This may be achieved by using tarps or enclosed vehicles and trailers.
- 2.4 All cut material should arrive and be installed as soon as possible. See "storage" below.

## 3.0 Storage

- 3.1 Cut material shall be installed within 24 hours of harvesting or it shall be stored and protected.
- 3.2 Store cut material submerged under water or under wet woven fabric and stored in the shade.
- 3.3 If longer storage is required, cut material may be stored with refrigeration at 34° f with 90% humidity, wrapped in wet burlap. Willow pole and stake cuttings shall be kept in refrigerator storage no longer then 5 days. Willow poles with stems and branches attached will be kept in storage no longer than 48 hours (i.e. brush layer material). All trimmed brush and branches shall be kept in storage no longer then 48
- 3.4 During planting the cuttings shall remain moist until installation using planting bags or buckets with water, vermiculite or equivalent.

## 4.0 Schedule

- 4.1 Planting of cuttings shall occur at the time of construction.
- 4.2 Cuttings installed during construction will require supplemental weekly watering until November 15 or until 6" of rain has fallen, whichever comes first.

## 5.0 Installation & Browse Protection

- 5.1 Install cuttings (live stakes or poles) as per planting details and
- 5.2 Plants shall be watered in and soaked immediately after planting or
- 5.3 All willow material that has splits, swelling, lesions or peeled bark

will be trimmed off and discarded.

SHEET

CANYON

FEIGE (BANK

SEP 4, 2015 AS SHOWN LW, JRH LW, JF LW

DATE:
SCALE:
MAPPING BY:
DESIGNED BY:
DRAFTED BY:
CHECKED BY:

OF 1

VERIFY SCALES
ONE INCH